

Please note the following addendum for the Bid Document Titled:

“2022 Paulding County Chip Seal Project”

ADDENDUM # 2

Item 1: Replace the current summary sheet with this new sheet. Project 3, Crane Township TR 69 was not the correct road. The correct road is TR 61 from CR 424 south to the end.

Item 2: Replace the bid sheets with these new one. Project 3, Crane Township, prime oil has been has been added.

Item 3: Replace sheet 1 with the attached. Project 3, Crane Township Road 2 has been updated. TR 61 is the correct road.

* Please acknowledge receipt of this addendum.

2022 PAULDING COUNTY CHIP SEAL PROJECT

The work for which this proposal is invited consists of nine projects:

Project 1. Paulding County

- | | |
|-------------------------------------------------------------------------------|---------------------------------------------------------------------------------|
| 1) Single Seal Coat-HFRS-2P
CR 201 from SR 637 to TR 10
(5287' x 19') | 3) Single Seal Coat – HFRS-2P
CR 71 from SR 500 to SR 111
(12,828' x 18') |
| 2) Single Seal Coat –HFRS-2P
CR 60 from CR 177 to SR 66
(15,900' x 19') | 4) Single Seal Coat – HFRS-2P
CR 128 from CR 138 to SR 66
(15,012'x18') |

Project 2. Emerald Township

- | | |
|---------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------|
| 1) <u>Single Seal Coat – HFRS-2P</u>
TR 168 from CR 123 to CR 111
(5268' - 18') | 2) <u>Double Seal Coat – MC30/HFRS-2P</u>
TR 224 from CR 133 to TR 139
(5354' x 16') |
|---------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------|

Project 3 Crane Township

- | | |
|---------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|
| 1) <u>Single Seal Coat – HFRS-2-P 2)</u>
TR 1030 from CR 424 to TR 1031
(1687' x 18') | 2) <u>Double Seal Coat-MC30/HFRS-2P</u>
TR 61 from CR 424 to end
(1035' x 12') |
| 3) <u>Single Seal Coat – HFRS-2P</u>
TR 1031 from TR 1030 to CR 424
(1530' x 18.5') | |

Project 4 Harrison Township

- | | |
|----------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| 1) <u>Double Seal Coat – MC30/HFRS 2-P</u>
TR 134 from SR 49 to East
(300'x 18') | 2) <u>Single Seal Coat –HFRS-2P</u>
TR 162 from TR 61 to Bridge
(1980' x 17') |
|----------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|

2022 Paulding County Chip Seal Project

Project 1 Paulding County

Item No.	Description	Quantity	Unit	Unit Price	Total Price
409	HFRS - 2P	42,172	Gallons		
409	Cover Aggregate Material, No. 8	1,308	Tons		
614	Maintaining Traffic	Lump	Sum		
					Total \$

Project 2 Emerald Township

Item No.	Description	Quantity	Unit	Unit Price	Total Price
408	Prime Coat, MC 30	3808	Gallons		
409	HFRS - 2P	13,945	Gallons		
409	Cover Aggregate Material, No. 8	266	Tons		
409	Cpver Aggregate Material, No. 67	129	Tons		
614	Maintaining Traffic	Lump	Sum		
					Total \$

Project 3 Crane Township

Item No.	Description	Quantity	Unit	Unit Price	Total Price
408	Prime Coat, MC30	552	Gallons		
409	HFRS-2P	7,702	Gallons		
409	Cover Aggregate Material, No. 8	152	Tons		
409	Cover Aggregate Material, No. 67	67	Tons		
614	Maintaining Traffic	Lump	Sum		
					Total \$

Project 4 Harrison Township

Item No.	Description	Quantity	Unit	Unit Price	Total Price
408	Prime Coat, MC30	240	Gallons		
409	HFRS-2P	2,171	Gallons		
409	Cover Aggregate Material, No. 8	58	Tons		
409	Cover Aggregate Material, No. 67	9	Tons		
614	Maintaining Traffic	Lump	Sum		
					Total \$

Project 5 Jackson Township

Item No.	Description	Quantity	Unit	Unit Price	Total Price
408	Prime Coat, MC30	8,906	Gallons		
409	Bituminous Material, HFRS-2P	23,680	Gallons		
409	Cover Aggregate Material, No. 8	346	Tons		
409	Cover Aggregate Material, No. 67	302	Tons		
614	Maintaining Traffic	Lump	Sum		
				Total	\$

Project 6 Washington Township

Item No.	Description	Quantity	Unit	Unit Price	Total Price
409	HFRS - 2P	5,507	Gallons		
409	Cover Aggregate Material, No. 8	171	Tons		
614	Maintaining Traffic	Lump	Sum		
				Total	\$

Project 7 Carryall Township

Item No.	Description	Quantity	Unit	Unit Price	Total Price
408	Prime Coat, MC30	6071	Gallons		
409	HFRS-2P	17,544	Gallons		
409	Cover Aggregate Material, No. 8	280	Tons		
409	Cover Aggregate Material, No. 67	206	Tons		
Special	Full Base, Chemical Stablized Base Course 12" Pass 1, 12" Pass 2, 21' wide	16,929	SY		
614	Maintaining Traffic	Lump	Sum		
				Total	\$

Grand Total \$
