

LEGAL NOTICE
Paulding Road Paving Improvements

Sealed bids will be received by the Board of County Commissioners of Paulding, Ohio, at 451 McDonald Pike, Paulding, Ohio, 45879 until **10:00 A.M., D.S.T. on November 12, 2025.**

Proposal 1: Paving Road Improvements I	Engineer's Estimate \$1,720,391
Proposal 2: Paving Road Improvements II	Engineer's Estimate \$457,527
Proposal 3: Paving Road Improvements III	Engineer's Estimate \$132,311

Completion Deadline for each proposal is November 30, 2025. Each proposal will be awarded separately.

Each bidder is required to furnish with its proposal, a Bid Guaranty and Contract Bond in accordance with Section 153.54 of the Ohio Revised Code. Bid security furnished in Bond form, shall be issued by a Surety Company or Corporation licensed in the State of Ohio to provide said surety.

Each Proposal must contain the full name of the party or parties submitting the proposal and all persons interested therein. The owner intends and requires that this project be completed as listed above.

All contractors and subcontractors involved with the project will, to the extent practicable use Ohio products, materials, services, and labor in the implementation of their project. Additionally, contractor compliance with the equal employment opportunity requirements of Ohio Administrative Code Chapter 123, the Governor's Executive Order of 1972, and Governor's Executive Order 84-9 shall be required.

Bidders must comply with the prevailing wage rates on Public Improvements in Paulding County as determined by the Ohio Bureau of Employment Services, Wage and Hour Division, (614) 644-2239.

All contractors shall follow all applicable Federal and State OSHA regulations. The contractor shall also hold the County Engineer harmless for any violations or fines received while engaged in this project.

All contractors must provide current Certificate of Liability Insurance Coverage for \$1,000,000 along with a current Certificate of Worker's Compensation Coverage, before they can be hired to perform any type of work for Paulding County.

All materials shall conform to the latest version of the State of Ohio Department of Transportation Construction and Material Specifications.

Sealed bids shall be in writing and in accordance with specifications furnished by Paulding County and on file in the Offices of the Paulding County Engineer and Commissioners.

Bids are to be sealed and addressed to the Clerk of the Board of Commissioners of Paulding County, Ohio, and bids on the above-named items to be marked:

PROPOSAL: "Paulding Road Improvements"

The Board of County Commissioners reserves the right to reject any and/or all bids received.

BY ORDER OF THE BOARD OF COUNTY COMMISSIONERS, PAULDING COUNTY, OHIO
Heather Barnhouse, Clerk Board of Commissioners

2025 Asphalt Paving Paulding County

The work for which this proposal is invited consists of the following projects:

Proposal 1 – Paving Road Improvements I, Grover Hill Wind Farm:

1) County Road 60 from TR 137 to SR 637 5,280' x 19'

Scope: This work will require placing a 1.5" surface course of SS 823 Asphalt Concrete. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 1.5" thick along the edge of the road and traffic will be maintained.

2) County Road 24 from TR 131 to SR-637 10,560' x 17'

Scope: This work will require placing a 2.5" intermediate scratch course of 441 Asphalt Concrete and a 1.5" surface course of SS 823 Asphalt Concrete. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 4" thick along the edge of the road and traffic will be maintained.

3) Latty Township Road 48 from TR 137 to SR-613 5,280' x 16'

Scope: This work will require placing a 2.5" intermediate scratch course of 441 Asphalt Concrete and a 1.5" surface course of SS 823 Asphalt Concrete. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 4" thick along the edge of the road and traffic will be maintained.

4) Latty Township Road 18 from TR 131 to 0.24 mi East 1,267' x 14'

Scope: This work will require placing a 0.5" intermediate scratch course and a 1.5" surface course of SS 823 Asphalt Concrete. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 2.0" thick along the edge of the road and traffic will be maintained.

5) Latty Township Road 12 from TR-131 to 0.50 mi East 2,640' x 18'

Scope: This work will require placing a 0.5" intermediate scratch course and a 1.5" surface course of SS 823 Asphalt Concrete. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 2.0" thick along the edge of the road and traffic will be maintained.

6) Latty Township Road 131 from TR-12 to TR-54

18,480' x 16'

Scope: This work will require placing a 1.5" intermediate scratch course of 441 Asphalt Concrete and a 1.5" surface course of SS 823 Asphalt Concrete from TR-12 to TR-48. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 3" thick along the edge of the road and traffic will be maintained.

This work will require placing a 0.5" intermediate scratch course and a 1.5" surface course of SS 823 Asphalt Concrete from TR-48 to TR-54. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 2.0" thick along the edge of the road and traffic will be maintained.

7) Latty Township Road 137 from CR-24 to CR-60

15,840' x 17'

Scope: This work will require placing a 0.5" intermediate scratch course a 1.5" surface course of SS 823 Asphalt Concrete from CR-24 to SR-114. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 2.0" thick along the edge of the road and traffic will be maintained.

This work will require placing a 1.5" intermediate scratch course of 441 Asphalt Concrete and a 1.5" surface course of SS 823 Asphalt Concrete from SR-114 to TR-60. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 3" thick along the edge of the road and traffic will be maintained.

Proposal 2 – Paulding County Paving:

1) Blue Creek Township – County Road 79 from CR-12 to SR-114

10,634' x 20'

Scope: This work will require placing a 0.5" intermediate scratch course and a 1.5" surface course of SS 823 Asphalt Concrete. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 2.0" thick along the edge of the road and traffic will be maintained.

2) Jackson Township – County Road 151 from TR-126 to CR-138

4,245' x 16'

Scope: This work will require placing a 0.5" intermediate scratch course and a 1.5" surface course of SS 823 Asphalt Concrete. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches

will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 2.0" thick along the edge of the road and traffic will be maintained.

3) Washington Township – County Road 197 from CR-60 to SR-66 5,692' x 16'

Scope: This work will require placing a 0.5" intermediate scratch course and a 1.5" surface course of SS 823 Asphalt Concrete. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 2.0" thick along the edge of the road and traffic will be maintained.

Proposal 3 – Brown Township Paving:

1) Brown Township Road 146 from TR-151 (S. End) to CR-171 7,762' x 12'

Scope: This work will require placing a 0.75" intermediate scratch course and a 1.5" surface course of SS 823 Asphalt Concrete. The surface course will be placed with a minimum depth of 1.5" over the crown or highest portion of the roadway. All driveway approaches will be paved and tapered sufficiently down to driveway grade when SS823 is laid. Item 617 compacted aggregate will be placed 1.5' wide and 2.0" thick along the edge of the road and traffic will be maintained.

The time for completion of these projects is November 30, 2025.

All invoiced work on Proposal 1, Proposal 2, and Proposal 3 shall be kept separate by Township and invoiced to the Paulding County Engineer's Office that way.

The right is reserved by the Board of County Commissioners to reject any and all Bids, to waive any informality in Bids received, and to accept any Bid which is deemed to be most favorable to the Board of County Commissioners. No Bidder may withdraw his Bid for a period of sixty (60) days after the scheduled closing time for the receipt of Bids.

ADVERTISING DATES: **October 27, 2025**
 November 3, 2025

BID OPENING: **November 12, 2025**

Scott A. Strahley, P.E., P.S.
Paulding County Engineer